

UNCLASSIFIED

AD NUMBER

ADB010439

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 12 APR 1976. Other requests shall be referred to Electrical Engineering Group, (1842ND), Scott AFB, IL.

AUTHORITY

EEG USAF notice, 23 Oct 1978

THIS PAGE IS UNCLASSIFIED

THIS REPORT HAS BEEN DELIMITED  
AND CLEARED FOR PUBLIC RELEASE  
UNDER DOD DIRECTIVE 5200.20 AND  
NO RESTRICTIONS ARE IMPOSED UPON  
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.



ADB010439

AD No. \_\_\_\_\_  
DDC FILE COPY

TECHNICAL REPORT

SURVEY OF 603 TACTICAL COMMUNICATIONS  
SQUADRON (TCS) GROUNDING SYSTEM  
AT SEMBACH AIR FORCE BASE, GERMANY

DDC  
RECEIVED  
APR 6 1976

ELECTRICAL/MECHANICAL BRANCH  
1842 ELECTRONICS ENGINEERING GROUP  
RICHARDS-GBAUR AFB, MO. 64039

409646

15 MARCH 1976

1842 EEG/EPEU-TR-76-6 ✓

## 1842 ELECTRONICS ENGINEERING GROUP

### MISSION

The 1842 Electronics Engineering Group (EEG) is organized as an independent group reporting directly to the Commander, Air Force Communications Service (AFCS) with the mission to provide communications-electronics-meteorological (CEM) systems engineering and consultive engineering for AFCS. In this respect, 1842 EEG responsibilities include: Developing engineering and installation standards for use in planning, programming, procuring, engineering, installing and testing CEM systems, facilities and equipment; performance of systems engineering of CEM requirements that must operate as a system or in a system environment; operation of a specialized Digital Network System Facility to analyze and evaluate new digital technology for application to the Defense Communications System (DCS) and other special purpose systems and equipment configurations to check out and validate engineering-installation standards and new installation techniques; providing consultive CEM engineering assistance to HQ AFCS, AFCS Areas, MAJCOMs, DOD and other government agencies.

ACC	IN for
NTIS	White Section <input checked="" type="checkbox"/>
OCG	Blue Section <input type="checkbox"/>
UNANNOUNCED	
JUST	
<i>Attch on file</i>	
BY	DISTRIBUTION/AVAILABILITY
Dist	APRIL 1977
<i>B</i>	

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. REPORT'S CATALOG NUMBER	
1842 EEG/EPEU TR 76-6		(9)	
4. TITLE (and Subtitle)		5. TYPE OF REPORT & PERIOD COVERED	
SURVEY OF 603 TACTICAL COMMUNICATIONS SQUADRON (TCS) GROUNDING SYSTEM AT SEMBACH AIR FORCE BASE, GERMANY,		TECHNICAL REPORT,	
6. AUTHOR(s)		7. PERFORMING ORG. REPORT NUMBER	
(10) JOHN F. ZYCH AND HAROLD D. McRANEY		(14) 1842 EEG/EPEU-TR-76-6	
8. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
1842 EEG/EPE/AFCS RICHARDS-GEBAUR AFB, MO. 64030			
11. CONTROLLING OFFICE NAME AND ADDRESS		12. REPORT DATE	
ELECTRICAL/MECHANICAL BRANCH 1842 EEG/EPEUE RICHARDS-GEBAUR AFB, MO. 64030		(11) 15 MAR 1976 (12/13p)	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		13. NUMBER OF PAGES	
SAME AS BLOCK # 11		15	
		15. SECURITY CLASS. (of this report)	
		UNCLASSIFIED	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report)			
<del>DOD AGENCIES ONLY</del> Distribution limited to J.S. Gov't. agencies only Test and Evaluation; 1 APR 1976. Other requests for this document must be referred to			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
DOD AGENCIES ONLY			
18. SUPPLEMENTARY NOTES			
NONE			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)			
NONE			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)			
SURVEY OF THE 603 TACTICAL COMMUNICATIONS SQUADRON (TCS) ON-SITE GROUNDING SYSTEM LOCATED AT SEMBACH AFB, GERMANY BY REPRESENTATIVES OF THE 1842 EEG AND THE 1839 ELECTRONICS INSTALLATION GROUP IN ORDER TO INVESTIGATE AND RECOMMEND CORRECTIVE ACTION TO ELIMINATE THE SOURCE OF 400 HERTZ "HUM" ON COMMUNICATION CIRCUITS BETWEEN THE 603 TCS AND 2134 COMMUNICATIONS SQUADRON TECHNICAL CONTROL FACILITY.			

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

APPROVAL PAGE

This report has been reviewed and is approved for publication and distribution.

DIVISION CHIEF: *Gerald T. Harris*  
GERALD T. HARRIS

BRANCH CHIEF: *Leo W. Dlugolecki*  
LEO W. DLUGOLECKI

PROJECT ENGINEER: *John F. Zych*  
JOHN F. ZYCH

PROJECT ENGINEER: *Harold D. McRaney*  
HAROLD MCRANEY

## SUMMARY

A survey of the grounding system, located at the 603 Tactical Communications Squadron (TCS) at Sembach AFB, Germany, was performed by representatives of the 1839 Electronics Installation Group (EIG) and the 1842 Electronics Engineering Group (EEG). The purpose of the 1839 EIG survey was to investigate and identify the source of 400 Hertz (Hz) "hum" on communication circuits between the 603 TCS and the 2134 Communications Squadron (CS) Technical Control Facility (TCF) at Sembach AFB. The purpose of the 1842 EEG survey was to further investigate and attempt to correct the 400 Hz "hum" on the communication circuits. The results of the survey indicated: an inadequate low impedance ground at the 603 TCS site; incorrect electronic equipment van power wiring (in which the neutrals and green safety wires were connected together); the existence of various independent ground systems; excessive currents floating on the skin of equipment vans; and incorrectly wired semi-permanent buildings. Modifications in the power wiring of the semi-permanent buildings were made along with minor grounding system changes. As a result, a decrease in the 400 Hz "hum" was noted in the circuits between the 603 TCS and the 2134 CS TCF.

## TABLE OF CONTENTS

<u>Para No.</u>		<u>Page</u>
1	Introduction	1
2	Procedures	1
3	Results	5
4	Recommendations	7

## LIST OF ILLUSTRATIONS

<u>Figure No.</u>	<u>Title</u>	<u>Page</u>
1	603 TCS Equipment Layout, Sembach AFB, Germany	2
2	Earth Resistance Values of Existing Ground System at 603 TCS	3
3	Test Equipment Setup for Earth Resistance Measurements	4
4	Proposed New Ground System Using Existing 50Hz Ground System	8

## 1. INTRODUCTION.

1.1 The 2134 Communications Squadron (CS) had reported excessive 400 Hz "hum" noise problems on communications circuits from the 603 Tactical Control Squadron (TCS). Both units are located at Sembach AFB, Germany. The 1839 Electronics Installation Group (EIG) was tasked with dispatching a team to investigate and determine the source of the problem. This team surveyed the Sembach problem during the week of 18 Nov 75 and reported the source of "hum" was caused by power neutral currents flowing on site grounds. Because of the scheduled "Creek Swap" project at Sembach AFB, it was determined that further investigation and corrective action should be taken to eliminate the 400 Hz "hum" on the communication circuits under investigation. As a result, two 1842 EEG engineers, Mr. John Zych and Mr. Harold McRaney, were sent to Sembach AFB, Germany to investigate and take corrective action to eliminate the 400 Hz "hum" problem.

1.2 The information in this report reflects the findings, recommendations, and results of only the 1842 EEG survey. However, the results are similar to those of the 1839 EIG.

## 2. PROCEDURES.

2.1 The procedures used to obtain the data contained in this report are as follows:

a. Grounding drawings were developed with the aid of on-site personnel and through visual inspection. Site layout is shown in Figure 1 and existing grounding drawings are shown in Figure 2.

b. Resistance-to-earth measurements were made with an Associated Research Model 259 Vibro-ground Tester at important grounding rod locations throughout the 603 TCS complex. Earth resistance values are shown in Figure 2. The three-point method shown in Figure 3 was used for these tests.

c. Currents in the major grounding conductors were measured with a "clamp-on" ammeter. Results of current readings found on various ground cables are shown in Figure 2.




Figure 1. 603 TCS Equipment Layout,  
Sembach AFB, Germany

---EXISTING FENCE

■ - 50 HZ COM POWER DISTRIBUTION PANEL  
○ - 60 HZ GEN POWER DISTRIBUTION PANEL




Figure 2. Earth Resistance Values of Existing Ground System at 603 TCS




Figure 3. Test Equipment Setup for Earth Resistance Measurements

d. A review of equipment schematics and a visual inspection of electrical wiring in various electronics vans was made to determine wiring configuration and to locate the green wire safety ground and neutral connected together at the wiring panels.

e. The level of the 400 Hz interference on the circuits was measured with an HP-3555 Transmission Test Set at the 2134 CS TCF and at the 603 Technical Control Van (AN/TCC-62). The measurements were made to determine the severity of the interference and to assess the results of modifications made to the site ground system during the survey.

### 3. RESULTS.

3.1 The results of the survey indicated a very poor site ground system. The measurements of ground rods showed the existence of a high earth resistance. The 603 TCS was unaware of this problem due to erroneous Base Civil Engineering (BCE) grounding measurements. The measurements had been made with all wires connected to the ground rods.

3.2 The TSQ-91, TSC-15, TSC-60, TRC-97, TPS-43, TSC-62 and TGC-28 vans are wired with all grounds tied together at the power distribution panels. The neutrals and green safety wires were connected together along with signal cable shields, signal reference grounds, and the skin of the shelter itself. This situation resulted in several amperes of current flowing in the various grounding conductors and the shelter skin which caused potential differences between the various equipments within the facility. The TRC-87 and TTC-30 have separate ground and neutral conductors as required.

3.3 The semi-permanent and permanent buildings on location all had power panels wired with the green safety wire and the neutral connected together. This situation introduced most of the current into the ground system. Current values of 10 amperes, 3 amperes, and 3.5 amperes were removed from the ground system when the green wires were isolated from the neutral.

3.4 Neutral wire conductors are being used as safety ground in the air conditioning (A/C) units on most of the vans. The A/C units operate at 3 phase, 208V, and use neutral as the safety equipment ground. This wiring introduces unnecessary current in the grounding system.

3.5 Neutrals and green safety wires are connected together at the utility outlets. This situation introduces current into the equipment's safety ground and is in violation of Section 210 of the National Electrical Code (NFPA No. 70).

3.6 The maintenance of ground systems is poor. Corroded and loose connections, many unnecessary taps, and frayed conductors were found throughout the grounding system.

3.7 Circuit measurements made during normal site operation indicated that high levels of 400 Hz interference (greater than -40 dBm) existed on many of the 603 TCS circuits routed through the 2134 TCF. The level varied from circuit-to-circuit and changed during the day as different equipments were turned on and off within the 603 TCF facility. During periods when the level of interference was greatest, a high level near one volt RMS was found to exist between pair and ground on all 603 TCS circuits within the 2134 CS TCF. The major cause of the interference in the channels is the conversion of the common mode interference voltage to a differential signal within the channel. This is due to the impedance unbalance inherent in the cables and equipments both at the 2134 CS TCF and the 603 TCS communications facility. The problem is aggravated by the fact that the primary power frequency is within the passband of the circuits involved. Thus, for the same level of interference in the communication channels, the 400 Hz power system requires an additional 30 to 40 dB of rejection over that required by 50/60 Hz power systems.

3.8 The noise measurements were repeated during a period when the 603 TCF facility was down for testing. The results indicated a 30 dB decrease in the average interference level. After modifications were made to the 603 TCF ground system, which reduced the ground currents

(see paragraphs 3.2 and 3.3), additional measurements of the interference levels were made. The results of this test showed a 10 to 20 dB decrease in the average interference level compared to the results of the initial tests run on the operational facility prior to the modifications.

#### 4. RECOMMENDATIONS.

4.1 Recommend that a new ground system be implemented at the 603 TCS. The ground system should be similar to the sketch in Figure 4. A low impedance (10 ohm or less) path-to-earth should be obtained, either by installing a new copper ground grid, or by using the existing 50 Hz ground system.

4.2 Recommend that 603 TCF obtain a Vibro-ground Tester and perform periodic ground resistance measurements on the ground systems. Ground resistance measurements should be made periodically on all permanent installations as well as at every temporary field installation. A goal of 10 ohms or less earth resistance should be obtained at all installations.

4.3 Recommend Unsatisfactory Report (UR) action be taken to have all neutrals and green protective grounds isolated within the vans. Neutral should be isolated from the equipment van shell and be grounded only at one location. This location should be at the power generation source. Only when the equipment vans are rewired can noise from the 400 Hz be completely eliminated. With a better grounding system, the quality of the circuits will be improved; however, some noise will still exist because of the neutral currents floating on the skins of the shelter.

4.4 Recommend that a complete analysis of site equipment configuration also be accomplished. Items such as common grounding, highest power consumers located near the power source, balancing of power loads to get neutral currents minimized, running power cables as short as possible, checking new equipment vans to insure neutral wire isolation grounding measurements, and maintenance of grounding system should be considered in the analysis.




Figure 4. Proposed New Ground System Using Existing 50 Hz Ground System

- |  |                                   |
|--|-----------------------------------|
| ■ - 50 HZ COM POWER DIST. PANEL                      | ----- EXISTING GROUND SYSTEM      |
| ○ - 60 HZ COM POWER DIST. PANEL                      | —— NEW GROUND CABLE               |
| ⊙ - CONNECTION TO 60 HZ COM POWER DISTRIBUTION PANEL | ○ — CONNECTION TO VAN OR BUILDING |

4.5 Recommend larger cables be used for the 603 TCF grounding system. The braided cable presently being used does not have a high current capability. It also has a large voltage drop and a tendency to fray easily. A larger stranded copper cable, such as a #2/0 AWG cable, is recommended for installation use. For field application, a larger braided cable may be used.

4.6 Recommend that a longitudinal balance test be made a part of the routine system checks and trouble-shooting procedures for the equipment and cables associated with the 603 TCS facility. This test is required since the recommended improvements in the grounding system will not totally eliminate pair-to-ground 400 Hz voltage. Circuit longitudinal balance must be depended upon to further reduce the interference to an acceptable level. Methods and equipment for performing longitudinal balance tests are specified in DCAC-310-70-51, Sup 1, Chapter 9. The balance value should exceed 70 dB to insure satisfactory system operation.

DISTRIBUTION: X

603 TCS .....	5
2134 CS .....	5
HQ AFCS .....	
EPE .....	20
EPCP .....	1
DAPL .....	5
NCA/EPE .....	5
SCA/EPE .....	5
PCA/XME .....	5
ECA/EPE .....	5
1839 EIG/EPE .....	5
DDC, CAMERON STATION, ALEXANDRIA, VA. ....	10